

SYSTEM APPROVAL

Product Name: Istidama 4wall SIP System



## **Conditions of Approval:**

- 1. The BDA Agrément BAW 18-079/01/A must remain valid.
- 2. The BDA Agrément BAW 18-085/01/A for Euroform Versaliner board must remain valid.
- 3. The product is to be used and installed in strict accordance with the BDA certification.
- 4. The system must be installed by installers who have been trained and approved by the certificate holder.
- 5. The system is limited to buildings up to 10m or three storeys high.
- 6. The wall panels and claddings / DPC details must meet the requirements of Chapter 7.3 of the Warranty Technical Manual.
- 7. If the external finish has a cavity, this must be drained and vented and formed in accordance with Chapter 7.3 of the Warranty Technical Manual.
- 8. Where there is no cavity, the condition listed in the Parex warranty approval ref 13 0019a must be adhered to and approved by the RMS on a site-by-site basis.
- 9. There must be a fully detailed structural design package submitted for approval for each project to confirm that the structural performance of the panels meets the requirements of Regulation 7 and Part A of the Building Regulations.
- 10. The arrangement of openings for windows and doors in the wall panels should be undertaken by either the factory or approved contractors following the manufacturer's details and a structural engineers design.
- 11. A suitable breather membrane & roofing must be provided to protect the SIP panels from water penetration through the claddings.
- 12. Projects with Balconies or parapets are not covered by this assessment. Any projects which include balconies and/or parapets are subject to project specific approval, with particular emphasis on how water penetration and rainwater disposal (through the panels) will be managed.
- 13. Site based manufacturing facilities of Istidama 4wall will require satisfactory assessment of quality control systems prior to production and installation.

Cert No: 4wall0618

Valid Until: 24<sup>th</sup> August 2019

**Summary:** Offsite built structural insulation panel wall system for use as walls for residential, non-residential, industrial and commercial buildings.

**Use:** This system is subject to a Structural Engineer's Report on a site-by-site basis.


# THE BUILDING STRUCTURE

## Structure and Building Design

The Istidama 4wall SIP System is an offsite building system, built in their factory, using a repeatable joint design for both the horizontal and vertical structural insulation

The panelling system provides the structural elements for all aspects of the external walls, with the approriate connectors.

The below shows the range of different sizes of 2.4m high structural wall panels;



Please note; an extensive series of various Lintel Panel Sizes, Window base panel sizes, standard window & door assemblies are available from the manufacturer.

## Panel

Each panel is made up of 2 skins of 12mm Versaliner MgO board and 161mm PU core, and are 185mm thick.

The MgO Board is bonded via Structurally Overpacked BASF PU foam pumped core 1mm profiled top hat galvanised steel female perimeter connection on all 4 sides.

Aluminium electrical cable conduits are installed as per design down the internal face of the board.

## Connections

- 12mm Euroform Versaliner MgO spines for panel joints and leg stiffness.
- 1mm profiled top hat galvanised steel male soleplate and head-binder
- Apollo joint adhesive
- 50mm long stainless steel temporary fastiners
- Jointing paste between internal and external vertical joists of MgO boards or MgO boards and other materials (variable)

## **External Finishes:**

- Insulated render carrier / render
- Insulated brick slip carrier / brick slips
- Timber cladding / cladding
- Brick / stone / cavity

#### **Internal Finishes:**

• Knauf 'air spray' thin coat plaster

#### **NB: Details**

Details of examples can be found in 9 of the BDA Agrément BAW 18-079/01/A.

Castle Chambers, 43 Castle Street, Liverpool, L2 9TL

## PLAN CHECKING TEAM

The following will be checked on a site-by-site basis by our plan check team.

| To be Reviewed   | Comments |
|--|----------|
| A1 Loading   |          |
| A2 Ground Movement   |          |
| A3 Disproportionate Collapse   |          |
| B1 Means of warning and escape   |          |
| B3 Internal fire spread (structure)  |          |
| B4 Boundary conditions   |          |
| B5 Access and Facilities for the Fire Service  |          |
| C1 Site preparation and resistance to contaminants.  |          |
| C2 Resistance to Moisture<br>Cladding finishes<br>Roof coverings<br>External doors and windows |          |
| G2 Water Efficiency  |          |
| H1 Foul Water Drainage (Below Ground)  |          |
| H3 Rainwater Drainage  |          |
| H6 Solid Waste Storage   |          |
| J2 Discharge of Product of Combustion (with regard to flue positioning).                       |          |
| L1 Conservation of Fuel and Power  |          |
| M1 Access and Use  |          |

## SITE INSPECTION

The following will be inspected on site by the Risk Management Surveyor.

| To be inspected   | Comments |
|---|----------|
| Foundations   |          |
| Drainage;<br>- Connection to house<br>- Plot drainage   |          |
| Foundation connection to panels   |          |
| Ground Floor;<br>- Gas Membrane, if required<br>- Sub-floor ventilation<br>- Sub-floor drainage   |          |
| Intermediate Floors;  |          |
| Connection of panels;<br>- Stitching external<br>- Stitching internal<br>- Party wall<br>- Connections  |          |
| Cladding  |          |
| Part B;<br>- Fire stopping to lines of compartmentation<br>- Spandrel Panels/roof fire stopping<br>- Means of escape,<br>- Fire detection/alarms and emergency lighting |          |
| Stair;<br>- Handrail<br>- Guarding  |          |
| Roof;<br>- Insulation/fire stopping at eaves<br>- Terminals   |          |
| Access to Plot for Part M   |          |
| Final Inspection  |          |

Castle Chambers, 43 Castle Street, Liverpool, L2 9TL

#### AS BUILT COMMISSIONING CERTIFICATES AND COMPLIANCE REPORTS REQUIRED AT COMPLETION

- The following certificates and reports are required at the completion of each dwelling to demonstrate compliance with the building regulations and warranty requirements.

| Information required prior to completion of works | Comments |
|---|----------|
| Sound test results (site performed)               |          |
| Ventilation commissioning certificates            |          |
| Gas appliance Commissioning Certificates          |          |
| As Built SAP Calculations                         |          |
| Air tightness test results                        |          |
| EPCs  |          |
| Operation & Maintenance Manual                    |          |
| Quality control document for each module          |          |

#### **Other Comments**

Castle Chambers, 43 Castle Street, Liverpool, L2 9TL

## PLANS AND DOCUMENTS

The plans and documents used to complete this assessment are as follows

Document Reference:BDA Agrément BAW 18-079/01/ABDA Agrément BAW 18-085/01/AAwall Offsite Hyper SIPS Walling System - Overview - Booklet 'A'PAREXTHERM Mineral - 4wall Hyper SIPS systemPAREXTHERM Mineral - 4wall Hyper SIPS system - cavity battenPAREXTHERM Acrylic Revlane - 4wall Hyper SIPS systemPAREXTHERM Acrylic Revlane - 4wall Hyper SIPS system - cavity batten